

4246151E  
Ynez Rd

Remove Exist 33kV KPF OH Switch  
Place 12kV XFMR to feed exist street lights

Relocate XFMR to 6151E  
New 33kV Pothead & Riser location

**Legend**

- Existing SCE Facilities —
- New Civil installed by SCE —
- New Civil installed by Customer w/ Easement —
- New Civil installed by Customer —

4246152E

4246153E

Install (2) 6" duct from 6152E to new 7'x18' Vault intercepting existing (4)5" & (2)6" duct bank. This civil portion will be SCE Cost Plus Install. Rule 15 to be used for Civil, cable and new 33kV UG Switch.

Install cable in exist duct from New Vault to V6551

Rule 16 Portion. Customer to extend (2) 6" duct from property line to location where New 33kV Transformer and Protection will be located. New 12kV Primary switchgear to be located adjacent.

V5506551

Ynez Rd

Motor Ca  
Pkwy

Extend (2) 6" duct from exist V6551 along parking structure to rear property line. (1) pulling structure may be req'd. This portion requires an easement. Customer to install civil and SCE to pull cable under Rule 15.

